KOLAR DIVISION.

Dated 3rd May 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. of 28th May 1928, for opening out a Feeder Channel to Vedulvani Tank, Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for opening out a feeder channel to Vedulvani Tank, Goribidnur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenders must quote specific rates for each item of work both in figures and words.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate of the cost of opening out a Feeder Channel to Vedalveni Tank, Goribidnur Taluk.

Items of work	Head sluice	Scouring sluice in the ancout.	Drop No. 1 & 2	Tunnel	Feeder Channel	Aqueduct	Constructing a small aquedet across Bommasandar Tank, sluice channel	Per	Total quantity	Rate	Cost
										Rs.	Rs.
Dismantling the old burnt brick masonry.	108	54	..	..	..	..		C.ft.	162		
Earthwork excavating foundation in soft rock.	33	..	..	..	600	62		C.yd.	695		
Concrete in surki mortar..	115	..	51	172	..	2,111		C.ft.	2,449		
Burnt brick in surki mortar.	895	..	134	..	..	3,183		"	4,212		
Burnt stone slabs 6" thick dressed.	119	18	22	..	..	434		Sq.ft.	623		
Cutting groove and channel inguide and cill slabs.	L. S.	..	..	..	..	..		L. S.	L. S.		
Teak wood beam ..	1·12	..	..	..	..	..		C.ft.	1·12		
Teak wood shutter with iron parts, gear rod 1¼" diameter with iron fittings, etc.	L. S.	..	..	..	..	..		L. S.	L.S.		
Plastering with surki mortar.	7·48	..	1·40	..	..	22·09		Sqr.	30·97		
Constructing rough stone revetment new.	19	..	20	34	..	41		C.yd.	114		
Constructing rough stone revetment old.	9	..	..	..	..	..		"	9		
Dismantling the old coping slab over the anicut and replacing.	..	24	..	..	..	..		Sq.ft.	24		
Benching rock ..	..	6	..	..	..	203		"	209		
Concrete in cement ..	..	10	..	..	..	..		C.ft.	10		
Burnt stone in surki mortar (old stone).	..	16	..	..	..	..		"	16		
Burnt stone in surki mortar (new stone).	..	8	..	161	..	..		"	169		
Cutting grooves in stone work.	..	3½	..	..	..	..		"	3½		
Bond stones ..	..	4·5	..	..	..	..		Sq.ft.	4 5		
Cement pointing ..	..	0·49	..	..	..	..		Sq.	0·49		
Cutting grooves in slab ..	..	9	..	..	..	..		S.ft.	9		
Teak wood shutter 1" thick including iron work.	..	14	..	..	..	..		Sq ft.	14		
Earthwork excavation ordinary soil.	..	..	21	33	5,196	13		C.yd.	5,263		
Pointing with surki mortar.	..	..	..	3·05	..	..		Sqr.	3·05		
Earthwork excavation hard rock.	..	..	..	..	200	..		C.yd.	200		
Turfing ..	..	..	..	..	8,074	..		Sq. yd.	80·74		
Providing Mile and furlong stones.	..	..	..	..	..	..		L. S	L. S.		
Earthwork excavation hard gravel.	..	..	..	..	..	79		C.yd.	79		
Arch work including centring charges.	..	..	..	..	..	1,112		C.ft.	1,112		
String course ..	..	..	..	..	..	64		R.ft.	64		
Cement wash and surki mortar plastering.	..	..	..	..	..	18·07		Sqr.	18.07		
Total ..	..	..	..	..	..	..	Lump sum rupees.	..	..		
Contingencies ..	..	..	..	..	..	..		..	..		
Grand Total ..	..	..	..	..	..	..		..	..		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.